



NOTES:

- △ 1. MUST BE 4 WIRE + EQUIPMENT GROUND PROVIDED BY OTHERS.
- 2. - - - - - = CABLING PROVIDED BY OTHERS.
- 3. INPUT OVERCURRENT PROTECTION AND WIRING MUST BE INSTALLED FOR A FULLY RATED 40kW SYMMETRA 3 PHASE. INPUT OVERCURRENT PROTECTION IS BASED ON 80% RATING ANY DEVIATION PLEASE CONTACT APC.
- △ 4. AC POWER CABLING IS 4 WIRE + EQUIPMENT GROUND AT 208VAC 3-PHASE.
- 5. INSTALLATION MUST COMPLY WITH ALL APPLICABLE NATIONAL AND LOCAL CODES.

THIS DRAWING AND SPECIFICATIONS HEREIN ARE THE PROPERTY OF SCHNEIDER ELECTRIC AND SHALL NOT BE COPIED, REPRODUCED OR USED IN WHOLE OR IN PART, AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION FROM SCHNEIDER ELECTRIC. THIS DRAWING IS BASED UPON LATEST AVAILABLE INFORMATION AND IS SUBJECT TO CHANGE WITHOUT NOTICE.



TITLE:
 INFRASTRUCTURE 40kW UPS
 INPUT: 208V, SINGLE FEED W/O XFMR
 OUTPUT: 208V, 3PH, 10kW
 SYSTEM ONE LINE DIAGRAM

PROJECT: STD SUBMITTAL DRAWINGS SHEET 1 OF 1

DWG NO: ISX-10K40C1F1NXF-SD

DRAWN BY: B ZAHN	17-DEC-09
ENGINEER: J RING/A WARNER	17-DEC-09
APPROVED BY: SHERIDAN/F DIOSA	17-DEC-09

REV: 5
 PROJ ANGLE
 N.A.