



- NOTES:
- △ 1. MUST BE 4 WIRE + EQUIPMENT GROUND PROVIDED BY OTHERS.
  - 2. - - - - - = CABLING PROVIDED BY OTHERS.
  - 3. INPUT OVERCURRENT PROTECTION AND WIRING MUST BE INSTALLED FOR A FULLY RATED 40kW SYMMETRA 3 PHASE. INPUT OVERCURRENT PROTECTION IS BASED ON 80% RATING ANY DEVIATION PLEASE CONTACT APC.
  - △ 4. AC POWER CABLING IS 4 WIRE + EQUIPMENT GROUND AT 208VAC 3-PHASE.
  - 5. INSTALLATION MUST COMPLY WITH ALL APPLICABLE NATIONAL AND LOCAL CODES.