



NOTES:

- △ 1. MUST BE 4 WIRE + EQUIPMENT GROUND PROVIDED BY OTHERS.
- 2. - - - - - = CABLING PROVIDED BY OTHERS.
- 3. INPUT OVERCURRENT PROTECTION AND WIRING MUST BE INSTALLED FOR A FULLY RATED 40kW SYMMETRA 3 PHASE. INPUT OVERCURRENT PROTECTION IS BASED ON 80% RATING ANY DEVIATION PLEASE CONTACT APC.
- △ 4. AC POWER CABLING IS 4 WIRE + EQUIPMENT GROUND AT 208VAC 3-PHASE.
- 5. INSTALLATION MUST COMPLY WITH ALL APPLICABLE NATIONAL AND LOCAL CODES.

	TITLE: INFRASTRUXURE 40kW UPS INPUT: 208V, SINGLE FEED, W/O XFMR OUTPUT: 208V, 3PH, 40kW SYSTEM ONE LINE DIAGRAM		DWG NO: ISX-40K40C1F1NXF-SD	REV: 5
	PROJECT: STD SUBMITTAL DRAWINGS		SHEET: 1 OF 1	APPROVED BY: SHERIDAN/F. DIOSA
	ENGINEER: J RING/A WARNER		DATE: 17-DEC-09	ANGLE: N.A.
	DRAWN BY: B ZAHN		DATE: 17-DEC-09	PROJ:

THIS DRAWING AND SPECIFICATIONS HEREIN ARE THE PROPERTY OF SCHNEIDER ELECTRIC AND SHALL NOT BE COPIED, REPRODUCED OR USED IN WHOLE OR IN PART, AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION FROM SCHNEIDER ELECTRIC. THIS DRAWING IS BASED UPON LATEST AVAILABLE INFORMATION AND IS SUBJECT TO CHANGE WITHOUT NOTICE.