

1-SHUNT TRIP

(110-125VAC/DC)

1 - AUX CONTACT

(1 FORM C + 1 BA)

DEVICE

QB

Q1

QSF

Q7

RATING

400AF, 600V

320A, 500VDC

3P DC

BREAKER

ABB

T5N320TWAS4



- INSTALLATION SHALL COMPLY WITH ALL APPLICABLE NATIONAL, STATE AND LOCAL CODES.
- REFER TO PRODUCT DOCUMENTATION FOR ADDITIONAL DETAILS PRIOR TO INSTALLATION AND SITE PREPARATION WORK.
- DRAWING DEPICTS POWER SYSTEM CONNECTIONS AND IS NOT REPRESENTATIVE OF PHYSICAL LAYOUT, PLEASE REFER TO MECHANICAL DRAWINGS FOR PHYSICAL LAYOUT.
- △ 4. MAXIMUM AVAILABLE FAULT CURRENT IS 30kAIC.
- △ 5. AC SOURCE TO BE 208VAC 3PH WYE 4 WIRE+GROUND (CONTACT Schneider Electric, IF OTHER). REFER TO SHEET-3 FOR RECOMMENDED OCPD RATINGS.
- △ 6. AC CABLING TO BE 600V RATED, 4 WIRE+GROUND.
- △ 7. SINGLE MAINS CONFIGURATION IS A DEFAULT. REFER TO SHEET-2 FOR DUAL MAINS.
- 8. THIS DRAWING SHOWS MINIMUM NUMBER OF XR BATTERY FRAMES.
- MAXIMUM (4) XR BATTERY FRAMES CAN BE BAYED TO UPS. Δ 9. DISTRIBUTION MODULES ARE NOT PART OF PDPM100F-M, CAN BE PURCHASED SEPARATELY FROM Schneider Electric.
- △ 10. SEE INSTALLATION MANUAL FOR RECOMMENDED SETTINGS.
- △ 11. REFER TO SHEET-3 FOR RECOMMENDED OCPD RATINGS.
- Δ 12. FOR PROPER INSTALLATION OF EPO, MIB BREAKER MUST BE INTERRUPTED UPON OF THE EPO BUTTON. A SHUNT TRIP COIL MAY THEREFORE BE NECESSARY FOR THIS PURPOSE. FOR MORE DETAILS, SEE EPO SECTION IN THE INSTALLATION MANUAL.


THIS DRAWING AND SPECIFICATIONS HEREIN ARE THE PROPERTY OF SCHNEIDER ELECTRIC AND SHALL NOT BE COPIED, REPRODUCED OR JSED IN WHOLE OR IN PART, AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION FROM SCHNEIDER ELECTRIC. THIS DRAWING IS BASED UPON LATEST AVAILABLE INFORMATION AND IS SUBJECT TO CHANGE WITHOUT NOTICE.



TITLE:		SYM	IMETR	A PX	100		
	INPU	T: 208		H, SI			NS
BO		FEED	WITH	PDU,	WITH	DUT	XFMR
	S١	STEM	ONE	LINE	DIAG	RAM	

PROJECT: SUBMITTAL DRAWINGS SHEET 1 OF 3

DWG NO: SY	100K100F1	3-PD-SD	^{REV.} 5
DRAWN:	JAYAPRAKASH	14-JAN-16	ANGLE
ENGINEER:	A WARNER/ F SYED	14-JAN-16	PROJECTION
APPROVED:	B.SHERIDAN	14-JAN-16	N.A



1-SHUNT TRIP

(110-125VAC/DC)

1 - AUX CONTACT

(1 FORM C + 1 BA)

DEVICE

QB

Q5

Q2

Q3

QSF

Q7

RATING

600AF, 480/277VAC

600AF, 480/277VAC

400AF, 480/277VAC

400AF, 480/277VAC

400AF, 600V

320A, 500VDC

ABB

BREAKER

T5N320TWAS4

LEGEND: AC CABLE - PROVIDED BY OTHERS

- 1. INSTALLATION SHALL COMPLY WITH ALL APPLICABLE NATIONAL, STATE AND LOCAL CODES.
- 2. REFER TO PRODUCT DOCUMENTATION FOR ADDITIONAL DETAILS PRIOR TO INSTALLATION AND SITE PREPARATION WORK.
- 3. DRAWING DEPICTS POWER SYSTEM CONNECTIONS AND IS NOT REPRESENTATIVE OF PHYSICAL LAYOUT. PLEASE REFER TO MECHANICAL DRAWINGS FOR PHYSICAL LAYOUT.
- Δ4. MAXIMUM AVAILABLE FAULT CURRENT IS 30kAIC.
- Δ 5. AC SOURCE TO BE 208VAC 3PH WYE 3 OR 4 WIRE+GROUND (CONTACT Schneider Electric, IF OTHER). REFER TO SHEET-3 FOR RECOMMENDED OCPD RATINGS.
- AC CABLING TO BE 600V RATED, 3 OR 4 WIRE+GROUND.
- Δ7. SINGLE MAINS CONFIGURATION IS A DEFAULT.
 - FOR DUAL MAINS CONFIGURATION REMOVE THE 3 SHORTING STRAPS/WIRES.
- THIS DRAWING SHOWS MINIMUM NUMBER OF XR BATTERY FRAMES. MAXIMUM (4) XR BATTERY FRAMES CAN BE BAYED TO UPS.
- DISTRIBUTION MODULES ARE NOT PART OF PDPM100F-M, CAN BE PURCHASED SEPARATELY FROM Schneider Electric.
- Δ10. SEE INSTALLATION MANUAL FOR RECOMMENDED SETTINGS.
- △11. REFER TO SHEET-3 FOR RECOMMENDED OCPD RATINGS.
- Δ12. FOR PROPER INSTALLATION OF EPO, MIB BREAKER MUST BE INTERRUPTED UPON OF THE EPO BUTTON, A SHUNT TRIP COIL MAY THEREFORE BE NECESSARY FOR THIS PURPOSE. FOR MORE DETAILS, SEE EPO SECTION IN THE INSTALLATION MANUAL.

THIS DRAWING AND SPECIFICATIONS HEREIN ARE THE PROPERTY OF SCHNEIDER ELECTRIC AND SHALL NOT BE COPIED, REPRODUCED OR USED IN WHOLE OR IN PART, AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION FROM SCHNEIDER ELECTRIC. THIS DRAWING IS BASED UPON LATEST AVAILABLE INFORMATION AND IS SUBJECT TO CHANGE WITHOUT NOTICE.



TITLE:	SYMMET	RA PX 100)
INF	PUT: 208V 3		
		208V 100I	
	A FEED WITH		
	SYSTEM ONE	. LINE DIA	GRAM

DWG NO: C	SY100K100F28	B-PD-SD	^{REV.} 5
DRAWN:	JAYAPRAKASH	14-JAN-16	ANGLE
ENGINEER:	A WARNER/ F SYED	14-JAN-16	PROJECTION
APPROVED:	B.SHERIDAN	14-JAN-16	N.A
	· · · · · · · · · · · · · · · · · · ·		

Symmetra® PX 100K UPS Frame Submittal Data - w/ Modular PDU - w/o Transformer

	UDC Dati								er AC I r Singl	•	4				AC Inp al Feed			External Battery System ⁵			AC C	Output		
,	UPS Rati	ng		Vol	tage	Cur	rent	Reco	ommen	dation	s ^{3, 9, 10}	Curi	rents	Rec	ommer	ndatio	ns ^{3, 9}			dations ^{3, 9}	^{3, 9} Current			
UPS Frame	Qty of 10kW Power					Full		100%	100%	80%	80%			100%	100%	80%	80%	Nominal VDC	kW	@ Nom. VDC				
Rating	Modules 8	kVA	kW	Input ¹	Output ²	Load	Max.6	OCPD	Cable			NOM.	Max. ⁷	OCPD	Cable	OCPD	Cable				100% OCPD	100% Cable	NOM.	Max. ⁷
	1	10	10	208	208	33	36	40A	1x 8	45A	1x 8	28	35	30A	1x 8	35A	1x 8	2x 192	11	28	30A	1x 8	28	35
	2	20	20	208	208	66	72	80A	1x 4	90A	1x 4	56	69	60A	1x 6	70A	1x 4	2x 192	22	56	60A	1x 6	56	70
≥	3	30	30	208	208	100	108	110A	1x 2	125A	1x 1	83	104	90A	1x 4	110A	1x 2	2x 192	32	84	90A	1x 4	84	105
a Š	4	40	40	208	208	133	144	150A	1x 1/0	175A	1x 2/0	111	139	125A	1x 2	150A	1x 1/0	2x 192	43	113	125A	1x 2	112	140
/10 Fra	5	50	50	208	208	166	180	200A	1x 3/0	225A	1x 4/0	139	174	150A	1x 1/0	175A	1x 2/0	2x 192	54	141	150A	1x 1/0	140	175
IŞ₹	6	60	60	208	208	199	216	225A	1x 4/0	250A	1x 250	167	208	175A	1x 2/0	225A	1x 4/0	2x 192	65	169	175A	1x 2/0	168	210
100kV A/100kW 100K Frame	7	70	70	208	208	232	252	300A	1x 250	300A	1x 350	195	243	200A	1x 3/0	250A	1x 250	2x 192	76	197	200A	1x 3/0	196	245
5 ,	8	80	80	208	208	266	288	300A	1x 350	350A	1x 400	222	278	225A	1x 4/0	300A	1x 300	2x 192	86	225	225A	1x 4/0	224	280
	9	90	90	208	208	299	324	350A	1x 400	400A	1x 500	250	312	300A	1x 250	350A	1x 400	2x 192	97	253	300A	1x 250	252	315
	10 ⁸	100	100	208	208	332	360	400A	1x 500	450A	2x4/0	278	347	300A	1x 300	350A	1x 500	2x 192	108	282	300A	1x 300	278	347

APC Symmetra® PX

Notes. 208Y/120 V (Transformerless) Modular PDU: PDPM100F-M

- 1. Mains Input source(s) must be 208V Wye solidly grounded. Contact Schneider Electric if other.
- 2. Output is either 208V Wye 3-wire + Ground or 4-wire + Ground. Bypass source shall be 4-wire +G.
- 3. Recommended cables are THHN AWG/kcmil minimum requirement in raceway, sized for 30°C environment, 75°C terminations, PFC load, and three (3) current carrying conductors per circuit. All cabling must comply with installation site conditions and any applicable Local or National Codes.
- 4. Either single feed MIB or dual feed BIB input for the bypass shall be 4-wire+G. Rectifier MIB input for Dual Feed shall be 3-wire +G. See respective one-line drawings for further clarification.
- 5. Contact Schneider Electric for assistance with all external battery designs. Maximum allowed DC cabling voltage drop is 1 VDC.
- 6. Electronic Input Current Limit
- 7. This is the UPS short time rating of 125% Overload for 10 minutes. Actual short time performance may be limited by the overcurrent protective device selected.
- 8. For maximum scalability or future expansion it is recommended that the UPS frames be installed at their full ratings see bold highlighted data
- 9. All OCPD's and cabling are by others.
- 10. Dual feed only for mains 1 input. See Bypass AC Input for mains 2 input.
- 11. OCPD = Over Current Protective Device
- 12. Final selections are responsibility of Engineer of record based on installed conditions and SCC/ Selective co-ordination/ arc-flash analysis.



SYMMETRA PX 100 INPUT: 208V 3PH	DWG NO:
OUTPUT: 208V 100kW WITH PDU, WITHOUT XFMR	DRAWN:
SITE PLANNING DATA	ENGINEER:

OWG NO: SY	REV. 1		
ORAWN:	BALAMURUGAN	05-JUN-15	ANGLE
ENGINEER:	A.WARNER	05-JUN-15	PROJECTION
APPROVED:	B.SHERIDAN	05-JUN-15	N.A