



NOTES:

1. INSTALLATION SHALL COMPLY WITH ALL APPLICABLE NATIONAL, STATE AND LOCAL ELECTRICAL REGULATIONS.
2. PLEASE REFER TO PRODUCT MANUALS FOR ADDITIONAL DETAILS PRIOR TO INSTALLATION AND SITE PREPARATION WORK.
3. MAINS 3x400/230V TN-S (PROVIDED BY OTHERS).
4. Q1 - Q6 WITH 2NO/2NC AUXILIARY CONTACTS.
5. Q7, Q8 DC RATED THERMAL MAGNETIC TRIP MOLDED CASE CIRCUIT BREAKER. WITH 24VOLT DC UNDERVOLTAGE RELEASE (UVR) AND 2NO/2NC AUXILIARY CONTACTS.
6. ALL AC POWER CABLING IS L1,L2,L3,N,PE.
7. UPS INPUT AND OUTPUT CONDUCTORS MUST BE IN SEPARATE CABLE RUNS.
- △8. UPS AND STATIC BYPASS WITHSTAND RATING (Icw) = 200kA.
9. PLEASE REFER TO THE INSTALLATION MANUAL FOR THE BREAKER SETTINGS OF Q1,Q3,Q4 AND Q5.
10. DC CABLING SHOULD BE SEGREGATED FROM AC CABLING.
- △11. SEE BATTERY INSTALLATION INFORMATION.
12. POWER WIRING AND CONTROL WIRING SHOULD BE SEGREGATED.
13. - - - - - = CABLING PROVIDED BY OTHERS.
14. ALL DATA IN THIS DRAWING PROVIDED FOR FULLY POPULATED UNIT.

THIS DRAWING AND SPECIFICATIONS HEREIN ARE THE PROPERTY OF SCHNEIDER ELECTRIC AND SHALL NOT BE COPIED, REPRODUCED OR USED IN WHOLE OR IN PART, AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION FROM SCHNEIDER ELECTRIC. THIS DRAWING IS BASED UPON LATEST AVAILABLE INFORMATION AND IS SUBJECT TO CHANGE WITHOUT NOTICE.



TITLE: SYMMETRA MW  
 Input: 400V 3PH SINGLE MAINS  
 Output: 400V 3PH 1x800kW  
 1MOD UPS WITH MBP AND BATTERY CABINET  
 SYSTEM ONE LINE DIAGRAM  
 PROJECT: SUBMITTAL DRAWINGS SHEET 1 OF 1

DWG NO: SYMF800K800H1C1-SD  
 DRAWN: BALAMURUGAN  
 ENGINEER: S.ANDERSEN  
 APPROVED: C.LARSEN  
 14-DEC-11  
 14-DEC-11  
 14-DEC-11

REV: 4  
 ANGLE  
 PROJECTION:  
 N/A