



NOTES:-

1. MAINS INPUT MUST BE WYE 3 PHASE 4WIRE + GROUND, PROVIDED BY OTHERS.
2. ALL AC OUTPUT POWER CABLING FROM UPS IS 3 WIRE + GROUND AT 400/415V AC.
3. POWER WIRING AND CONTROL WIRING SHOULD BE IN SEPERATE CONDUITS.
4. CABLING PROVIDED BY OTHERS.
5. INSTALLATION MUST COMPLY WITH NATIONAL AND LOCAL CODES.

THIS DRAWING AND SPECIFICATIONS HEREIN ARE THE PROPERTY OF AMERICAN POWER CONVERSION AND SHALL NOT BE COPIED, REPRODUCED OR USED IN WHOLE OR IN PART, AS THE BASIS FOR THE MANUFACTURE OR SALE OF ITEMS WITHOUT WRITTEN PERMISSION FROM APC. THIS DRAWING IS BASED UPON LATEST AVAILABLE INFORMATION AND IS SUBJECT TO CHANGE WITHOUT NOTICE.

TITLE:	SILCON 320kW UPS SYSTEM WIRING DIAGRAM 320kW, 400/415V AC, 4NDDL	DWG NO:	SLJ320KHC4-WD	REV.	-
PROJECT:	SUBMITTAL DRAWING	DRAWN:	JAVAPRAKASH	05/04/02	SCALE: NTS
SHEET	1 OF 1	CHECKED:	MUND S/K KATO	05/04/02	PROJECTION
		ENGINEER:	S MACH	05/04/02	

